

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 8W	F9
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 03/30/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F9) Quarter corner common to Sections 21 and 28. 1850 - Established by Wells Burt, Deputy Surveyor, midway and on the Section line between Section corners 39.95 chains east and west. Set Maple post. Fir 6" N37W 24 links, Fir 10" S20E 17 links. 1965 - Remonumented by F.J.Bray, RLS at the position of a scribed wood post set by Harold Lawrence. Set 1" iron pipe with 4" aluminum cap. 18" Hemlock S20E 32.5 links, 12" S.Maple N36W 13.5 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F9) Found the 1965 monument in good condition and at record bearing and distance from the 12" S.Maple NBT NW, now 16" DBH, in good condition. The NBT Hemlock SE was not recovered. Accepted the monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F9) Fd. 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 16" Maple N37W 9.25' mrkd "1/4S" 1965 NBT
 10" Hemlock S81W 17.05' "1/4S NBT"
 6" Maple S22W 7.3' do
 12" Maple N88W 20.9' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 05/11/2009
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971