

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 8W	F7
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephan J. Szyszkoski, in a field survey on 03/31/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F7) Quarter corner common to Sections 16 and 21. 1850 - Established by Wells Burt, Deputy Surveyor, midway and on the Section line between Section corners 39.90 chains east and west. Set Sugar post. Cedar 9" N55W 21 links, W.Birch 9" S40E 10 links. 1967 - Billy D. Buckler RLS replaced the corner "at a wood post, midway and on line between two Section Corners. Found no evidence of Original Corner, but found squared post in place. Corner lies on South edge of a woods road". Set 1" pipe with 4" aluminum cap. 6" Aspen S65W 33.0', 48" W.Pine Stub N70W 91.6'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F7) Found the 1967 monument in good condition. The Aspen NBT SW is gone. Any evidence of the W.Pine Stub NBT NW was obscured by snow this date. I used the position of this monument to subdivide Section 21.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F7) Fd. 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:  
 6" Spruce N20W 27.03'      mrkd "1/4S NBT"  
 13" Aspen S57E 4.35'      do  
 5" Spruce N31E 52.2'      do  
 10" Spruce N66E 63.4'      do  
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 05/11/2009  
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities