

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 8W	E9
	T 48N R 8W	G8
2. Property Controlling in Section	T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5			4		3		2				1
3													
4	7	8			9		10		11				12
5													
6	18	17			16		15		14				13
7													
8	19	20			21		22		23				24
9													
10	30	29			28		27		26				25
11													
12	31	32			33		34		35				36
13													

I, Stephan J. Szyszkoski, in a field survey on G8 03/31/2009 do hereby state

that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E9) Corner common to Sections 20-21-28-29. 1850 - Established by Wells Burt, Deputy Surveyor. Set Hemlock post. Hemlock 12" N65E 11 links, Fir 10" S50W 19 links. 1967 - Remonumented by Billy D. Buckler RLS: "replaced as set by H. Lawrence, RLS. Found remains of a hemlock stump in approximate position for a B.T.". Set 1" pipe with 4" aluminum cap. 10" Balsam S27W 36.8', 10" Soft Maple N01E 91.3'.

(G8) Quarter corner common to Sections 21-22. 1850 - Established by Wells Burt, Deputy Surveyor, midway and on the Section line between Section corners 39.94 chains north and south. Set Sugar post. Sugar 4" N85W 7 links, Sugar 12" N18E 13 links. 1965 - Reestablished by F.J.Bray RLS midway and on line between Section corners. Set 1" I.pipe with 4" aluminum cap. 10" Elm N63W 73 links, 9" Elm S07W 13.5 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E9) Found the 1967 monument in good condition. The 10" Balsam NBT SW was not recovered. The 10" Soft Maple NBT N01E was not searched for. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

(G8) Found the 1965 monument in good condition. Both 1965 NBTs are now gone. Used the position of the monument to subdivide Section 21.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E9) Fd. 1"ID I.pipe with 4" alum. MI Dept of Conservation cap. Set measuring nail with MDNR tag in the side of:
 5" Cedar N12W 13.4' mrkd "S20 NBT"
 6" Maple S60W 1.55' "S29 NBT"
 7" triple Maple S53E 7.15' "S28 NBT"
 5" Balsam N37E 30.85' "S21 NBT"
 Bearings are magnetic.

(G8) Fd. 1"ID I.pipe with 4" alum. MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:
 4" Balsam N47W 3.96' mrkd "1/4S NBT"
 3" Balsam N80W 4.52' do
 10" Spruce S04E 47.2' do
 12" Spruce S45E 86.2' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 05/11/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

