

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T _____ R _____		_____
	T _____ R _____		_____
2. Property Controlling in Section	S 21 T 48N R 8W		3
	S 21 T 48N R 8W		10
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		_____
	S _____ T _____ R _____		_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

03/24/2009

03/24/2009

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20	●	21		22		23		24	
9					●								
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(3-Sec. 21) North 1/16 corner between Sections 20 and 21. Not established in the original survey.

(10-Sec. 21) South 1/16 corner between Sections 20 and 21. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(3-Sec. 21) Established the corner midway and on the section line between Quarter corner 1313.85' south and Section corner 1313.85' north.

(10-Sec. 21) Established the corner midway and on the section line between Quarter corner 1317.80' north and Section corner 1317.80' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(3) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.  
 Set measuring nail with MDNR tag in the side of:  
 8" twin Maple S43E 3.3' mrkd "N1/16 BT"  
 6" Maple S40W 8.55' do  
 6" Maple N77W 18.4' do  
 16" Maple N18W 18.9' do  
 Bearings are magnetic.

(10) Set an 8" spike with plastic cap driven into the root of a 24" W.Pine on which the position for the corner falls.  
 Set measuring nail with MDNR tag in the side of:  
 18" Hemlock S28E 13.26' mrkd S1/16 BT"  
 24" W.Pine N10E 1.88' do  
 20" Hemlock S86E 18.32' do  
 6" B.Spruce N83W 10.78' do  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 05/11/2009



For the Michigan Department of Natural Resources, Office of Land and Facilities