

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>21</u> T <u>48N</u> R <u>8W</u>	<u>15</u>
	S <u>21</u> T <u>48N</u> R <u>8W</u>	<u>11</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims	<u>15</u> <u>03/24/2009</u>	
	<u>11</u> <u>03/31/2009</u>	

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 11 03/31/2009 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

(15-Sec. 21) West 1/16 corner between Sections 21 and 28. Not established in the original survey.

(11-Sec. 21) Southwest 1/16 corner, Section 21. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(15-Sec. 21) Established the corner midway and on the Section line between Section corner 1318.30' West and Quarter corner 1318.30' East. The corner falls on the north edge of an E-W trail.

(11-Sec. 21) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(15) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 14" W.Pine S35E 38.3' mrkd "W1/16 BT"  
 10" Cedar S45W 28.55' do  
 10" Cedar North 11.85' do  
 12" Y.Birch N65E 21.4' do  
 Bearings are magnetic.

(11) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 12" W.Pine S66W 10.38' mrkd "SW1/16 BT"  
 20" Hemlock N35W 22.3' do  
 15" Maple S32E 13.02' do  
 11" Maple N42E 22.51' do  
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 05/11/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

