

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 48-49 N.R. 9W


Luce COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 1-2-35-36

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 7/19/68

WITNESSES TO CORNER..... 6" Tamarack (S NBT) S86°E 54.9'



10" Dead J. Pine (NBT) N24°W 13.5'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established by single proportionate measure
along East - West township line.
Found very old blazes along this line.

SURVEYOR'S SEAL

Billy D. Buckler
SIGNED Billy D. Buckler, R.L.S. DATE 9/13/68
REGISTERED LAND SURVEYOR