

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 48-49 N.R. 8-9W


Luce COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 1-6-31-36; also a township corner.

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 7/19/68

WITNESSES TO CORNER..... 12" Red Pine (S6 48-8 MBT) S76°E 12.1'



12" Red Pine (S1 48-9 MBT) S60°W 16.3'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced at wood post with original pine B.T.; bearing N70°E 07 links. Pine down with both faces burned with some scribe marks in evidence. Found 28" W. Pine stub bearing S17°E 14.3', scribed "Town Corner".

Corner lies on a red pine ridge $\frac{1}{2}$ chain North of marsh.

Corner found L. Rubick, Forestry Aide, Newberry.

SURVEYOR'S SEAL

Billy D. Buckler
SIGNED Billy D. Buckler R.L.S. DATE 9/12/68
REGISTERED LAND SURVEYOR