

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 48 N. R. 9W


Luce COUNTY

DESCRIPTION OF CORNER Meander corner between Secs. 3-10

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 7/16/68

WITNESSES TO CORNER..... 7" Cedar (MC NET) N59°W 13.7'



8" Tamarack (MC NET) S34°W 13.0'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from one original B.T.; a W. Pine down and in poor condition, bearing N59°W 32 lks.

Corner lies in water's edge.

Found and placed with L. Rubick, Forestry Aide.

37.0' S. of 74, 99 chs. W.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler
Billy D. Buckler R.L.S. DATE 9/12/68
REGISTERED LAND SURVEYOR