

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 47-48 N.R. 9W


Luce COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 5-6 T47N R9W & 31-32 T48N R9W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 2/20/64 with Forestry Aide, Aubick

WITNESSES TO CORNER..... 16" W. Pine (S5 NBT) S32°E 65 Lks.



18" W. Pine (S6 NBT) S35°W 82 Lks.

AND

CIRCLE CORNER REGISTERED

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This Corner was replaced from scribed Wood Post at stump of Corner tree. Pipe with Aluminum Cap was driven in stump. Found following Original B.T.'s.

- W. Pine 20", S86°W, 46 Lks (stump)
- W. Pine 18", S44°W, 18 Links (stump)
- 16" W. Pine as corner tree, (stump)

**SURVEYOR'S SEAL**

SIGNED Frank J. Bray DATE 8/17/1964  
REGISTERED LAND SURVEYOR