

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 47-48 N. R. 97


Luce COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Secs. 6, T47N R9W & 31, T48N R9W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 3/25/64 with Forestry Aide Dubick, Hinds & Alatalo

WITNESSES TO CORNER..... 8" W. Pine ( $\frac{1}{4}$  S NBT) S13°W 31 lks.



14" W. Pine ( $\frac{1}{4}$  S NBT) N30°E 98 $\frac{1}{2}$  lks.

AND

CIRCLE CORNER REGISTERED

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This Corner was placed on Line and the Single Proportioned distance between Town corner 1/2 mile West and Section Corner 1/2 mile East.

SURVEYOR'S SEAL

SIGNED Frank Bray DATE 8/11/1964  
REGISTERED LAND SURVEYOR