

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 48-49 N. R. 9W


Luce COUNTY

DESCRIPTION OF CORNER  $\frac{1}{4}$  Corner between Secs. 1-36

CORNER MONUMENT 1" pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED 7/19/68

WITNESSES TO CORNER..... 13" Red Pine ( $\frac{1}{4}$ S NBT) N72°W 11.7'



13" Red Pine ( $\frac{1}{4}$ S NBT) South 23.3'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner re-established by single proportionate along East-West town line.

Found no evidence of the original corner.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*  
Billy D. Buckler R.L.S. DATE 9/13/68  
REGISTERED LAND SURVEYOR