

#29

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
 Luce

(County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 9W	K1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S 1 T 48N R 9W	1
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Stephan J. Szyszkoski, in a field survey on June 26, 1995, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(K1) Corner common to Section 1-2 T48N-R9W and Section 35-36 T49N-R9W. Corner reestablished in 1968 by Billy D. Buckler, RLS as follows: "this corner re-established by single proportionate measure along East-West line. Found very old blazes along this line. Corner monument 1" pipe with 4" aluminum cap. Witnesses are 6" Tamarack S86E 54.9', 10" Dead J. Pine N24W 13.5'." Found no subsequent record.

(1-Sec. 1) West 1/16 corner between Section 1 T48N-R9W and Section 36 T49N-R9W. Corner established in 1968 by Billy D. Buckler, RLS: Placed 1" pipe with 4" aluminum cap and witnessed by 18" W. Pine N87E 33.5', 15" R. Pine S49W 29.5'. found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K1) Found and accepted Buckler's monument, as described, in good condition, and at record bearing and distance from his two 1968 accessories. Left the monument in place and marked two new witnesses as described below.

(1-Sec. 1) Found and accepted Buckler's monument, as described, in good condition, and at record bearing and distance from his 1968 accessories. The W. Pine is in good condition, the R. Pine is dead but standing. Left the monument in place, re-marked the 1968 W. Pine, and marked 3 new witnesses as described below.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K1) Found 1" pipe with 4" aluminum cap. Blazed, scribed, and set measuring nails in the following:

8" Tamarack S86E 52.95' "S1"
 4" Tamarack N05E 61.4' "S36 N8T"
 3" Spruce S62E 16.5' "S1 N8T"
 Placed a 3" squared Tamarack post adjacent. Bearings are magnetic.

(1) Found 1" pipe with 4" aluminum cap. Blazed, scribed, and set measuring nails in the following:

24" W. Pine N87E 34.1' (1968 witness)
 4" Spruce N64E 11.7' "W1/16 BT"
 12" R. Pine S10E 16.8' "W1/16 BT"
 12" W. Pine S79W 32.0' "W1/16 BT"
 Placed a 3" squared W. Pine post adjacent and a location poster at an E-W trail about 109' north. Bearings are magnetic.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Signed by Stephan J. Szyszkoski Date 8/29/95
 Surveyor's Michigan License No. 33986

