

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 & 48 N.R. 10W


Luce COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 2, 3 T47N R10W and 34, 35 T48N R10W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 3/17/64

WITNESSES TO CORNER..... 2" J. Pine (S2 NBT) S16°E 130 lks.



3" J. Pine (SX NBT) N71°E 34 lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by placing on Line and Single Proportioned measurement between Town Corner to East and 1/4 Corner 2 1/2 miles to West.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 8/17/1964
REGISTERED LAND SURVEYOR