

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 47 & 48 N.R. 10W


Lucas COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 5-6 T47N R10W & 31-32 T48N R10W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 3/18/64

WITNESSES TO CORNER..... 8" J. Pine (S5 NBT) S38°E 165 lrs.



6" J. Pine (S32 NBT) N88°E 148 lrs.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by placing on Line and Single Proportioned distance between 1/4 Corner $\frac{1}{2}$ mile to East and Town Corner 1 mile to West.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 8/17/1964
REGISTERED LAND SURVEYOR