

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 48-49N N.R. 10W


Luce COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 1-2-35-36

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 9-8-70

WITNESSES TO CORNER..... 13" hemlock (S36 NBT) N88°E 19.5'



10" Hemlock (S36 NBT) N17°E 34.5'

AND

CIRCLE CORNER REGISTERED

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner replaced at a 2" pipe, placed by Marcus Schaaf, R.L.S.  
Found a Y. Birch B.T., S59°E, 23 lks, tree is green. Faces have been  
chopped out several years ago, exposing the original markings.  
Found a Y. Birch tree, which appears to be a bearing tree, N45°E, 34 lks.  
Record indicates this tree to be Beech.  
Cor. lies in the south-west corner of a recent logging operation.

SURVEYOR'S SEAL

SIGNED

*Billy D. Buckler*  
Billy D. Buckler  
REGISTERED LAND SURVEYOR

DATE 9-21-70