

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 48N N.R. 10-11W


Luce COUNTY

DESCRIPTION OF CORNER 1/4 Cor. bet. Secs. 7-12

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 8-25-70

WITNESSES TO CORNER..... 16" W. Pine (1/4 S NBT) N81°W 42.8'



9" W. Pine (1/4 S NBT) S45°E 46.2'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner lies in South margin of swamp.

This cor. replaced from remains of two original witnesses; a cedar, bearing N39°E, 39 lks, tree is down, shattered and in poor condition, found face and notch with overgrown callous in place and a cedar stump, bearing N75°W, 19 lks. Stump is cut low, no identifying marks.

Found by L. Rubick, Forestry Aide, on 6/14/66.

SURVEYOR'S SEAL

Billy D. Buckler
SIGNED Billy D. Buckler, R.L.S. DATE 8-31-70
REGISTERED LAND SURVEYOR