

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 48N N.R. 10-11W


Luce COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 7-18-12-13

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 8-25-70

WITNESSES TO CORNER..... 3" Tamarack (NBT) N35°E 34.2'



No other living trees near

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from one original witness; a tamarack stub, bearing N53°E, 57 links.

Found face, notch and scribe marks in good condition.

We found what we think was the point of the original wood post deep in the mud. Corner lies in a wet, sphagnum marsh. Found no evidence of use at this corner.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler
Billy D. Buckler

REGISTERED LAND SURVEYOR

DATE

8-31-70