

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Luce  
 \_\_\_\_\_  
 (County)

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey	T48N R 10W	D11
	T48N R 10W	E13
	T_____ R_____	_____
	T_____ R_____	_____
2. Property Controlling in Section	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____
3. Miscellaneous Property in Sec.	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Jan 31 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

(D11) Quarter corner common to Sections 29 and 32. 1957 - Billy D. Buckler remonumented the corner at the position of a found wood post and at record bearing and distance from the remains of an original BT Maple N70E 5 links. Set 1" pipe with 4" brass cap. 11" Hemlock N35E 65 links, 14" Beech S27W 80 links.

(E13) Corner common to Sections 32-33 T48N-R10W and Sections 4-5 T47N-R10W. 1966 - Frank J. Bray RLS reestablished the corner by single proportionate measurement. Set 1" Iron pipe with 4" aluminum cap. 14" W.Pine N57E 687 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(D11) Recovered the 1957 monument in good condition and at record bearing and distance from the 1957 NBTs. The NBT Hemlock is in good condition with overgrown blazes. The NBT Beech is standing but is now dying. Made new witnesses as described below.

(E13) Recovered the 1966 monument in good condition and at record bearing and distance from the 1966 witness W.Pine, now a dead stump with no marks showing. This corner falls in a large open swamp. Made new witnesses as described below.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(D11) Found 1" ID I. pipe with 4" brass Mich. Dept of Conservation cap. Set measuring nails in:  
 18" Hemlock N40E 43.15' mrkd "1/4S" \*  
 8" Hemlock S83E 8.4' mrkd "1/4S NBT"  
 5" Maple N39W 26.5' do  
 5" Maple S42E 10.25' do  
 Set cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. \* denotes 1957 NBT.

(E13) Found 1" ID I. pipe with 4" aluminum MDNR cap. Set measuring nails in:  
 20" W.Pine N52E 390.82' mrkd "S33 NBT"  
 6" Tamarack N40W 224.02' "S32 NBT"  
 6" W.Pine S88W 444.94' "S5 NBT"  
 5" Tamarack S25E 210.38' "S4 NBT"  
 Bearings are magnetic. Distances are to nail with tag, were measured with EDM and are horizontal.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 2/9/05