

✓

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


_____ Luca _____ COUNTY
T _____ 48N _____ R _____ 11W

DESCRIPTION OF CORNER Sec. Cor. common to Secs 5-6-7-8

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 3/20/72

WITNESSES TO CORNER..... 8" Cedar (S5 NBT) N25°E 22.0'



7" Cedar (S8 NBT) S70°E 19.5'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced at a wood post, placed by H.C. Lawrence, R.L.S.
Remains of both original witnesses in proper position as recorded; Cedar 12"
S40°W 20 Links and Tamarack 12" N24°W 24 links
Corner lies in wet tag alder swamp with small Cedar.
Original township Sub-division by Geo. H. Cannon, D.S. June and July, 1853 and
was recorded as a Correctional Survey.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler
Billy D. Buckler

DATE

6/29/72

DISTRIBUTION:

REGISTERED LAND SURVEYOR

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68