

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Luce COUNTY
T 48N R 11-12W

DESCRIPTION OF CORNER ¼ Cor. bet. Secs. 6-1

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 3/20/72

WITNESSES TO CORNER..... 15" W. Pine (4S NBT) N7°E 52.5'



8" Cedar (4S NBT) N43°E 32.7'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from one original witness; a Y. Pine Stub with face and scribe marks bearing, N26°E 67 Links.

No evidence of second witness a Y. Pine 12"; N7°W 76 Links. This corner marked by Sam A Burt, D.S., Sept. 13, 1841. ¼ Corner lied in open marsh, 40' South of a Pine ridge.

SURVEYOR'S SEAL

SIGNED

Billy D. Buckler
Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 6/20/72

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68