

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 48N N.R. 11W


Luce COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 10-11-14-15

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 8-25-70

WITNESSES TO CORNER..... 14" W. Pine (S10 NBT) N74°W 33.2'



13" R. Pine (S15 NBT) S31°W 31.9'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from one W. Pine B.T., which is a stump with remains of trunk lying on ground. Found face and scribe marks in fair condition. Stump bears S63½° E, 28 lks.

Also found the defaced corner, witnesses, which were 1½ chs. South and 3.0 chs. west of the corrected corner.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*
Billy D. Buckler DATE 8-31-70
REGISTERED LAND SURVEYOR