

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 48N N. R. 11W


Luce COUNTY

DESCRIPTION OF CORNER ¼ Cor. bet. Secs. 8-9

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 8-28-70

WITNESSES TO CORNER..... 12" W. Pine (¼S NBT) N85°E 20.3'



9" W. Pine (¼S NBT) N26°W 48.9'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced at an old wood post. Found no evidence of original spruce witnesses. Distance checks well to an original corner ¼ mile north and to nearby swamp edges.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*
Billy D. Buckler REGISTERED LAND SURVEYOR DATE 9-22-70