

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 48N N.R. 11W


Luce COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 4-5-8-9

CORNER MONUMENT 1" pipe with 4" aluminum pipe

DATE MONUMENT PLACED AND WITNESSED 8-26-70

WITNESSES TO CORNER..... 12" Cedar (S4 NBT) N30°E 17.0'



8" Cedar (S5 NBT) N85°W 27.6'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from two original cedar witnesses, at the bottom of a cedar which was recorded as the corner tree.

Found Cedar, bearing S79°W, 8 lks, down and in fair condition.

Found Cedar, bearing S47°E, 8 lks, green and standing; size was recorded as 11" and is now 24".

Found scribe marks on both faces in excellent condition.

The original surveyor, when scribing this witness tree, apparently had broken the arc blade or pivot, on his scribe.

Found all the arc segments missing.

SURVEYOR'S SEAL

SIGNED Billy D. Buckler DATE 8-31-70
REGISTERED LAND SURVEYOR