

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 48 NR 11W

Luce COUNTY

DESCRIPTION OF CORNER Sec. Cor. 23-24-25-26

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 14" W. Pine (S23 NBT) N72°W 95 Lks.

14" W. Pine (S25 NBT) S32°E 135 Lks.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced cor. from one Tamarack B.T. bearing N39°E 25 Lks. Tree dead but standing and in good condition. Bearing tree is scribed "T48 NR11W S24 NBT." Cor. placed and wit. 2/18/59 with R. Norkoli, D.F. and L. Rubick.

SURVEYORS SEAL

Billy D. Buckler
SIGNED Billy D. Buckler DATE 8/5/59
REGISTERED LAND SURVEYOR