

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 48. NR. 11. W

L u c e COUNTY

DESCRIPTION OF CORNER 1/4 corner between Section 15 and 16.

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap.

WITNESSES TO CORNER 6" Hard Maple (1/4s NBT) N 20° E 65 1/2 Links

9" Sugar Maple (1/4s NBT) S 60° E 04 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED. This corner was replaced by measuring from old corner
(found Hard Maple B. T. S 70° W 30 Links from old corner, defaced)
1.40 chains east and 02 Links north as noted in the correctional
survey 1853. Found Yellow Birch line tree 10.11 chains to north
of corner.

Corner was placed and witnessed January 7, 1960 with R. Norkali,
G. Hamilton, L. Rubick.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR

Billy D. Buckler

DATE 2/23/60