

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Lucé Co.

4 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>48</u> N. <u>X</u> , R. <u>11</u> W.	D-1
2. PROPERTY CONTROLLING IN SECTION <u>5</u>	, T. <u>48</u> N. <u>X</u> , R. <u>11</u> W.	1-Sec.5, 7-Sec.5 4-Sec.5
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____, R. _____ E. _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 6-5-79 & 6-11-80, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- D-1 Quarter Corner for Sec's. 5, T48N R11W and Sec. 32, T49^N R11W, set by John Burt, D.S. in 1841. Bearings were: Spruce 12", N50°E, 22 lks. & Fir 10", N50°W, 16 lks.
- 1-Sec.5 West 1/16 Corner on North side of Sec.5.
- 7-Sec.5 North 1/16 Corner between Sec's. 4-5.
- 4-Sec.5 North-West 1/16 Corner of Sec. 5.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- D-1 Restored corner midway and on line bet. two Sec. Cors. Found an iron pipe, 6.0' South and 5.0' West. This is not a Marcus Schaaf R.L.S. pipe. Do'nt believe this pipe was intended for the 1/4 corner.
- 1-Sec.5 Placed corner midway bet. 1/4 Cor. to East and Sec. Cor. to West.
- 7-Sec.5 Placed corner 1.0' North of an 18" Pine Stub with blazes. Half mile measures 2,739.1' Record is 2,748.9'.
- 4-Sec.5 Placed corner 1,326.6' South of the North section line and on a line parallel to the West line.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Buried 1" pipe with 4" aluminium cap at D-1, Placed 1" pipe with 4" aluminium cap at 1/16 Cors. Bearings:
- D-1 Buried in South edge of E-W fireland. 15" R. Pine, S14°W, 21.4' & 12" R. Pine, N53°W, 40.1'.
- 1-Sec.5 8" R. Pine, N52°E, 23.0' & 9" W. Pine, S47°E, 38.4'.
- 7-Sec.5 16" W. Pine, N40°W, 10.7' & 14" W. Pine, S17°W, 18.5'.
- 4-Sec.5 8" S. Maple, S60°W, 18.8' & 13" S. Maple, N8°W, 26.4'. Corner lies 50' North of road.

SIGNED BY _____ DATE 10-9-80

Billy D. Buckler

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____

MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET