

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Luce Co.

2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>48</u> N. <u>11</u> W.	I-4
2. PROPERTY CONTROLLING IN SECTION <u>10</u>	T. <u>48</u> N. <u>11</u> W.	3
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-21 & 8-24, 19 84, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- I-4 East 1/4 Corner of Section 10. Wood Post. Spruce 7", N72°W, 36 lks. & Spruce 6", S51°E, 24 lks. Old 1/4 Corner: Cedar 8", S62°E, 26 lks. & Spruce 9", West, 27 lks. (36 lks West and 37 lks North - Old 1/4 effaced).
- 3 North 1/16 Corner on the West side of Section 10. Not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-4 Found Cedar B.T. effaced at the time of the G.L.O. Resurvey. Set D.N.R. Monument according to the relationship of the re-surveyed 1/4 corner to the effaced 1/4 cor. as recorded in the re-survey notes. G.L.O. notes call for an 18" Cedar L.T. 678.48' North of this 1/4 corner. Found said L.T. 678.23' North.
- 3 Set M.P.O.L. between the West 1/4 corner and the N.W. section corner of section 10.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
D.N.R. Monument set at both corners. Bearings:

- | | |
|----------------------------|--|
| I-4 6" Cedar, S61°W, 14.3' | 3 8" W. Pine, S81°E, 31.0' |
| 6" Cedar, N58°W, 16.1' | 7" R. Pine, N48°E, 51.9' |
| 6" Cedar, N02°W, 11.0' | 11" R. Pine, N21°W, 37.2' |
| 6" Cedar, N25°E, 20.3' | 6" R. Pine growing over root of 9" W. Pine, S15°W, 33.0' |

SIGNED BY _____

David B. Babbitt
David B. Babbitt

DATE 9-17-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)