

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

2 Corners

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>48</u> N. <u>11</u> E.	<u>K-3, G-3</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ E. S. _____ R. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. S. _____ R. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-21 & 8-24, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
 K-3 S.E. Section Corner of Section 2. Wood Post. OBT'S: Y. Birch 15, S39°E, 10 lks. & Balsam 10, N25½°W, 18 lks. Notes of C.C.I. Corp. dated 1956 to 1960. Found Y. Birch O.B.T. and set post. N.B.T.'S. : Hemlock 14", S17°W, 18.5 lks. & Beech 10", S70°E, 40.5 lks.

G-3 S.E. Section Corner of Section 4. Wood Post. OBT'S: W. Pine 16", S53°W, 8 lks. & Spruce 8", N71°E, 12 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

K-3 Found Sq. Cedar Post. Both C.C.I. NBTS in place with bearings and distances exact. The Hemlock NBT was down and rotten.

G-3 Set from 16" W. Pine OBT, S53°W, 8 lks. Tree is down quite rotten and badly burned but part of the upper face still shows (no scribing - burned off). Stream call 1 ch. North is good. Going South on line between Sections 9 and 10 found 17" W. Pine L.T. at 10.22 chs., and a 15" W. Pine L.T. at 30.63 chs. Both are down and rotten but with hack marks still plain on both. Both line trees are at prop. mea. for the 1/2 mile and about on line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 D.N.R. Monument set at both corners. Bearings:

K-3 16" Hemlock, West, 15.2'
 10" Hemlock, N75°W, 29.4'
 12" Hemlock, N43°E, 41.8'
 16" Beech, S59°E, 26.6'

G-3 6" Tamarack, N40°W, 29.4'
 6" Tamarack, S50°W, 36.1'
 10" W. Pine, S49°E, 35.4'
 7" Spruce, N67°E, 22.0'

SIGNED BY

David B. Babbitt

David B. Babbitt

DATE 9-17-84

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: