

# LAND-CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Luce Co.

3 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION <u>3</u>	, T. <u>48</u> N. S., R. <u>11</u> E. W.	<u>2, 14, 16</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____	, RECORDED PLAT _____	_____
5. PRIVATE CLAIMS _____	_____	_____

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 12-12 & 12-13, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 2 East 1/16 Corner on north side of section 3. Not prev. set.
- 14 South 1/16 corner on east side of section 3. Not prev. set.
- 16 East 1/16 corner on south side of section 3. Not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 2 Corner set M.P.O.L. between the North 1/4 Corner and the N.E. Section Corner of Section 3.
- 14 Corner set M.P.O.L. between East 1/4 Corner and S.E. Section Corner of Section 3.
- 16 Corner set M.P.O.L. between South 1/4 Corner and S.E. Section Corner of Section 3.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D.N.R. Monument set at all three corners. Bearings:

- 2 10" W. Pine, N03<sup>0</sup>W, 7.1' & 12" W. Pine, S83<sup>0</sup>E, 42.6' & 10" W. Pine, S18<sup>0</sup>E, 37.85' & 5" W. Pine, S30<sup>0</sup>W, 18.5'.
- 14 8" Tamarack, N78<sup>0</sup>E, 45.8' & 5" Tamarack, N49<sup>0</sup>W, 14.2' & 7" Tamarack, S37<sup>0</sup>E, 36.2' & 6" Spruce, S28<sup>0</sup>W, 41.7'.
- 16 7" Spruce, S26<sup>0</sup>W, 16.9' & 6" Spruce, N16<sup>0</sup>E, 10.5' & 7" Spruce, S59<sup>0</sup>E, 8.5' & 7" Spruce, S21<sup>0</sup>E, 17.1'.

SIGNED BY

*David B. Babbitt*  
David B. Babbitt

DATE 3-4-85

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)