

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

2 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>48</u> N. <u>8</u> , R. <u>11</u> E. <u>W.</u>	<u>I-1 &amp; H-1</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. _____ S., R. _____ E. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. _____ S., R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 12-12, 1984, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- I-1 Northeast Section Corner of Section 3. Wood Post. O.B.T.'S.: Hemlock 22, N8<sup>0</sup>E, 14 lks. & Maple 5, N40<sup>0</sup>W, 15 lks. & Hemlock 26, S32<sup>1</sup>/<sub>2</sub>W, 17 lks. & Cedar 10, S25<sup>1</sup>/<sub>2</sub>E, 33 lks.
- H-1 North 1/4 Corner of Section 3. Wood Post. O.B.T.'S.: Hemlock 14, N27<sup>0</sup>E, 27 lks. & Hemlock 7, N50<sup>0</sup>W, 45 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-1 Set by single proportion to the original gov't. survey record. Feature ties north and south indicate that the original position of this section corner was probably a little north of this point but are not definite enough for actual proof, therefor, it was set by single proportion.
- H-1 Set M.P.O.L. between the N.E. and N.W. section corners of sec. 3. Found iron bolt with nut on top 96.4' S10<sup>0</sup>W of this point but it is not compatible with other known corner positions in the area therefor I did not accept it as marking the true 1/4 corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D.N.R. Monument set at both corners. Bearings:

- I-1 10" W. Pine, N52<sup>0</sup>W, 29.1' & 12" W. Pine, S75<sup>0</sup>E, 30.25' & 12" Cedar, S47<sup>0</sup>E, 28.35' & 5" Cedar, S18<sup>0</sup>E, 6.05'.
- H-1 6" Hemlock, S61<sup>0</sup>E, 34.85' & 12" W. Pine, S44<sup>0</sup>W, 28.0' & 10" Cedar, N87<sup>0</sup>W, 8.1' & 6" Hemlock, N53<sup>0</sup>W, 8.0'.

SIGNED BY

David B. Babbitt

David B. Babbitt

DATE 3-4-85

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)