

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

3 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>48</u> ^{N.} / _{S.} , R. <u>11</u> ^{E.} / _{W.}	<u>G-1 Witnesses</u>
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____, ^{N.} / _{S.} , R. _____, ^{E.} / _{W.}	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____, ^{N.} / _{S.} , R. _____, ^{E.} / _{W.}	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 12-17-84 & 2-28-85, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- G-1A Witness Corner 559.94' West to Northwest Corner of Section 3. Not prev. set.
- G-1B Witness Corner 472.07' North to N.W. Corner of Section 3. Wood Post. O.B.T.'S.: Spruce 7, S20°W, 48 lks. & Tamarack 9", S45½°E, 42 lks.
- G-1C Witness Corner 430.52' East to N.E. Corner of Section 4. Not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-1A Set corner on the north section line of section 3, 559.94' east of the N.W. Sec. Cor. of sec. 3. The section corner falls in a small lake.
- G-1B Set corner on the west section line of section 3, 472.07' south of the N.W. sec. cor. of sec. 3. The section corner falls in a small lake.
- G-1C Set corner on the north section line of section 4, 430.52' west of the N.E. sec. cor. of sec. 4. The section corner falls in a small lake.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D.N.R. Monument placed at all three corners. Bearings:
- G-1A 18" W. Pine, N40°E, 47.5' & 18" W. Pine, East, 19.9' & 8" W. Pine, S23°E, 23.9' & 12" W. Pine, S02°E, 26.7'.
 - G-1B 6" W. Pine, S83°E, 30.8' & 3" W. Pine, S20°E, 15.3' & 6" W. Pine, S08°W, 43.0' & 4" W. Pine, S21°W, 74.7'.
 - G-1C 24" W. Pine, S18°E, 57.0' & 24" W. Pine, S06°W, 25.9' & 22" W. Pine, N88°W, 27.3' & 12" W. Pine, N65°W, 60.7'.

SIGNED BY _____

David B. Babbitt
David B. Babbitt

DATE 3-1-85

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: