

**LAND CORNER RECORDATION CERTIFICATE
FILING REQUIREMENT OF ACT 74, MICH. P.A.1970**

3 Corners

Luce Co.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 48 N. S., R. 11 W.	G-3
2. PROPERTY CONTROLLING IN SECTION	4, T. 48 N. S., R. 11 W.	15 & 16
3. MISCELLANEOUS PROPERTY IN SECTION	, T. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 1-24, 19 86, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- G-3 South 1/4 corner of Sec. 4 OBT'S: Cedar 12, N21°E, 21 lks. & Cedar 10, S42°W, 20½ lks.
- 15 West 1/16 corner on South side of section 4. OBT'S not prev. set.
- 16 East 1/16 corner on South side of section 4. OBT'S not prev. set.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- G-3 Corner set M.P.O.L. between Southwest Sec. Cor. and Southeast Sec. Cor. of Section 4 Cedar stps. in area but could not identify OBTS.
- 15 Corner set M.P.O.L. between Southwest Sec. Cor. and South 1/4 Cor. of Sec. 4.
- 16 Corner set M.P.O.L. between South 1/4 Cor. and Southeast Sec. Cor. of Sec. 4.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

DNR Monuments set at all three corners, bearings:

- G-3 20" W. Pine, S40°W, 42.8' & 14" Cedar, N68°W, 24.8' & 8" Cedar, N20°E, 17.3' & 12" Cedar, East, 6.2'.
- 15 7" Cedar, S8°E, 42.5' & 7" Cedar, S24°W, 38.3' & 12" Cedar, S82°W, 31.9' & 16" Tamarack, N35°E, 31.9'.
- 16 6" Cedar, N55°E, 19.0' & 7" Cedar, S85°E, 18.9' & 7" Cedar, S10°E, 31.0' & 6" Cedar, N58°W, 26.6'.

SIGNED BY

David B. Babbitt
David B. Babbitt

DATE 5-14-86

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)

FOR STATE AND UNITED STATES AGENCIES: