

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T <u>48N</u> R <u>11W</u>	E1	
	T <u>49N</u> R <u>11W</u>	<u>E13 (same corner)</u>	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10				12		
5													
6	18		17		16					14		13	
7													
8	19		20					22		23		24	
9													
10	30				28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 07/08/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Section corner common to 4-5 T48N-R11W and 32-33 T49N-R11W. 1841 - Established by John Burt, Deputy Surveyor. Set post. W.Pine 12" N57E 36 links, W.Pine 12" N55W 5 links. 1957 - Remonumented by Billy D. Buckler RLS: "Replaced Section corner as set by Marcus Schaaf, Reg. Surveyor. Found 2" iron pipe. Found W.Pine stump bottom bearing N57E 36 links. Corner lies in intersection of north and west fire lane". Set 1" pipe with 4" brass cap. 12" W.Pine N27W 64.5 links, 10" W.Pine S40E 68 links, 11" W.Pine N55E 96 links. 1980 - Remonumented by Billy D. Buckler RLS: "Replaced corner which was removed by logging traffic. Found remains of a concrete block 2' deep in soil" [this would be conc. base of Schaaf monument - sjs]. Set 1" pipe with 4" alum. cap. 1957 bearing trees were found in good condition in 1980, and at record bearing and distance. Found no other record of the Schaaf survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Recovered the 1980 monument, a 1" ID I.pipe with 4" alum. MDNR cap in good condition and at record bearing and distance from the three 1957 witnesses, all in good condition with overgrown blazes. Accepted the monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 1" ID I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 19" W.Pine N27W 43.5' mrkd "S32" 1957 NBT
 17" W.Pine S33E 44.95' "S4" do
 18" W.Pine N54E 63.75' "S33" do
 8" Spruce S59W 39.6' mrkd "S5 NBT"
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 02/17/2009
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Office of Land and Facilities

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971