

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Luce Co.

Two Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>49</u> ^{N.} S. , R. <u>8</u> ^{E.} W.	<u>B-10</u>
2. PROPERTY CONTROLLING IN SECTION <u>30</u>	T. <u>49</u> ^{N.} S. , R. <u>8</u> ^{E.} W.	<u>9-Sec.30</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ ^{N.} S. , R. _____ ^{E.} W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 12/9, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- B-10 Center Corner of Section 30.
- 9-Sec.30 East 1/16 Corner, Section 30.


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- B-10 Placed corner at intersection of lines connecting opposite Quarter Corners.
- 9-Sec.30 Placed corner midway bet. Center Corner to West and Quarter Corner to East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Placed 1" pipe with 4" aluminium cap at both corners.
- B-10 New Bearings: 6" Jack Pine, N28°E, 41.1' and 6" Jack Pine, S60°E, 35.7'.
Corners lies on edge of small marsh.
- 9-Sec.30 New Bearings: 8" W. Pine, S87°E, 26.0' and 12" W. Pine, S06°W, 10.25' and 8" Spruce, N54°W, 13.25'.

SIGNED BY Billy D. Buckler DATE 4-10-78
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8827



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____