

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Luce Co.

5 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>49</u> N. <u>X</u> , R. <u>8</u> W.	C-2, C-3, B-3, B-4, B-5
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-9, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration: Corners set by Wells Burt D.S. 1850
- C-2 $\frac{1}{4}$ Cor. bet. Sec's. 5-6. Bearings: Cedar 6, S15°W, 11 lks. & Spruce 8, N38°E, 27 lks.
 - C-3 Sec. Cor. 5-6-7-8. Bearings: Spruce 10, S64°E, 9 lks & W. Pine 14, N61°W, 29 lks.
 - B-3 $\frac{1}{4}$ Cor. bet. Sec's. 6-7. Bearings: Spruce 6, N81°E, 23 lks. & Tamarack 4, S47°W, 17 lks.
 - B-5 $\frac{1}{4}$ Cor. bet. Sec's. 7-18. Bearings: Y. Birch 6, S73°E, 8 lks. & Fir 12, N59°W, 16 lks.
 - B-4 Center Corner of Section 7.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- C-2 Corner re-established by single proportionate measure. Found no evidence of original cor.
 - C-3 Corner replaced from W. Pine stump, identified as an original bearing tree. Found a 2" pipe, 30.0' South and 2.9' East of true corner position.
 - B-3 Corner replaced from Tamarack B.T. in good condition.
 - B-5 Corner re-established by single prop. meas. No evidence of original cor.
 - B-4 Corner placed at intersection of lines connecting opposite quarter corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Placed 1" pipe with 4" aluminium cap at all corners.

- C-2 New Bearings: 12" W. Pine, N42°W, 6.8' and 10" W. Pine, S41°E, 13.5'
- C-3 New Bearings: 10" R. Pine, N21°W, 7.2' and 10" W. Pine, N73°E, 8.4'
- B-3 New Bearings: 11" R. Pine, N66°E, 35.5' and 12" R. Pine, N38°W, 20.3'
Corner lies in North margin of a small Spruce Bog.
- B-5 New Bearings: 14" Hemlock, S5°W, 70.5' and 12" Hemlock, N7°W, 30.3'
- B-4 Bearings: 12" W. Pine, N45°W, 26.4' and 8" R. Pine, S37°W, 22.3'

See sketch on Reverse Side.

SIGNED BY Billy D. Buckler DATE 12-17-75
Billy D. Buckler

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____