

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION



# LAND CORNER RECORD

T. 48-49N N.R. 8W


Luce COUNTY

DESCRIPTION OF CORNER Sec. Cor. common to Secs. 5-6-31-32

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 8-12-70

WITNESSES TO CORNER..... 12" Soft Maple (S31 NBT) N60°W 12.1'



15" Hemlock (S5 NBT) S30°E 16.9'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced at a scribed wood post, set by H. Lawrence, R.L.S.  
Found three original witnesses still in place; a Maple stub, bearing N50°W 25 lks.  
a dead Beech, bearing S40°W 26 lks. and a Y. Birch stump, bearing East 9 lks.  
(this witness recorded as N10°E in the field notes).

Corner lies on a steep NW slope, of a narrow ridge.  
Corner found by L. Rubick, Forestry Aide.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*  
BILLY D. BUCKLER  
REGISTERED LAND SURVEYOR

DATE 8-24-70