

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

LUCE

(County)

Located In:

Corner Code #/

1. Public Land Survey	T	49N	R	8W	B-6
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S	18	T	49N R 8W	8
	S		T		
3. Miscellaneous Property in Sec	S		T		
	S		T		

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Gerald L. Wiggins in a field survey on 12-6 & 12-8, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	17	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- B-6 Center of Section 18. Set by Billy D. Buckler, R.L.S. on 6-6-77.  
 8 West 1/16 Corner of Section 18. Not previously set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- B-6 Marked new witnesses.  
 8 Corner set midpoint on line between center corner and west 1/4 corner of section 18.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 B-6 DNR Monument.


8 1" pipe with plastic RLS Cap.

14" W. Pine, S27°E, 50.3'  
 10" Maple, N88°W, 22.95'  
 6" Maple, N38°E, 24.7'  
 8" Maple, N65°E, 24.5'

14" W. Pine, N76°W, 55.3'  
 10" W. Pine, S45°W, 35.6'  
 12" W. Pine, S20°E, 28.9'  
 12" W. Pine, N82°E, 46.5'

Signed by Gerald L. Wiggins  
 Surveyor's Michigan License No. 23521

Date 6-26-91



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS