

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Luce Co.

3 Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>49</u> <sup>N.</sup> <del>S.</del> , R. <u>9</u> <sup>E.</sup> <del>W.</del>	K-5, M-6, K-4
2. PROPERTY CONTROLLING IN SECTION _____	T. _____, S. _____, R. _____, E. _____, W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____, S. _____, R. _____, E. _____, W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5-4, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- K-5** Section Corner 11-12-13-14, set by Harvey Mellen, D.S. in 1850.  
Bearings were: Spr. Pine 5", N56°E, 12 lks. and Spr. Pine 14", S62°W, 38 lks.
- M-6** East 1/4 Corner, Section 13, set by Wm. A. Burt, D.S. in July 13, 1840.  
Bearings were: Spruce 4", S15°W, 30 lks. and Pine 14", N17°W, 8 lks.
- K-4** Quarter Corner bet. Sec's. 11-12, set by H. Mellen, D.S. in 1850.  
Bearings were: Spr. Pine 5", N56°E, 12 lks. and Spr. Pine 14", S62°W, 38 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-5** Found corner as placed by D.C. DeLaMater, R.L.S. (10/29/52). Monument in place. Bearing tree, red pine 20", N19°W, 30.0' has been cut about 1958.
- M-6** Found 2" Iron Pipe set in concrete in East edge of road by Marcus Schaaf, R.L.S.
- K-4** Found original bearing tree, S62°W, 38 lks. and a 2" pipe buried in fire lane. New bearings marked in 5/22/59 have been removed by logging operation.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-5** Re-Witnessed Corner.  
New Bearings: 9" Red Pine, N43°E, 37.7'.
- M-6** Witnessed corner as found.  
New Bearings: 16" Red Pine, N86°E, 21.0' and 15" Red Pine, N60°W, 50.4' and 15" Red Pine, S47°W, 79.5'.
- K-4** Re-Witnessed Corner.  
New Bearings: 5" J. Pine, S37°E, 13.1' and 7" J. Pine, N67°E, 18.4'.

SIGNED BY Billy D. Buckler  
Billy D. Buckler

DATE 1/27/77

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_

DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_

DATE \_\_\_\_\_

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 26, 1971  
REVISED MAY 14, 1975

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET