

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970
LUCE COUNTY

3 corners

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>49</u> N. <u>9</u> W. <u>9</u> S. R. <u>9</u> E. W.	J-3
2. PROPERTY CONTROLL- 2 ING IN SECTION _____	T. <u>49</u> N. <u>9</u> W. <u>9</u> S. R. <u>9</u> E. W.	I3-SEC. 2 I4-SEC. 2
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. S. _____ R. _____ W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Billy D. Buckler, RLS, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 3/15/76, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- J-3; South Quarter Corner, Sec. 2, set by Harvey Mellen, D.S. 1850.
Bearings were:
Spruce Pine I2", N16°E, 9 Lks. and S. Pine IO", SIW, 43 Lks.
 - I3-SEC.2; South-East I/I6 Corner, Sec. 2, 49-9.
 - I4-SEC.2; South I/I6 Corner, on East side, Sec. 2.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- J-3; Corner re-established midway and on line bet. two Sec. Cors.
No evidence of Original Corner.
 - I3-SEC. 2; Corner placed at intersection of lines, quartering the South-East quarter Section.
 - I4-SEC. 2; Corner placed midway bet. ¼ Cor. to North and Sec. Cor. to South.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- J-3; Placed I" Pipe with 4" Aluminum Cap, at Corner.
New Bearings: o
8" W.Pine, N38E, 29.8' and 8" J.Pine, N47W, 19.8'.
 - I3-SEC. 2; Placed I" Pipe with 4" Aluminum Cap, at Corner.
Bearings:
8" R.Pine, SI8E, 15.7' and I2" R.Pine, N47W, 33.8'.
 - I4-SEC. 2; Buried I"X36" Iron Pipe in East rut of N.-S. Road.
Bearings:
I2" R.Pine, N87E, 19.6' and I2" R.Pine, N46W, 35.1'.

SIGNED BY Billy D. Buckler DATE 9/27/76

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887.

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)



SURVEYOR'S MICHIGAN REGISTRATION NO. _____