

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

LUCE COUNTY

3 corners

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>49</u> ^{N.} S. , R. <u>9</u> ^{W.} E.	<u>K-5; M-6; K-4;</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____, S. _____, R. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____, S. _____, R. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, RLS., do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 5/4/76., 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- K-5; Section Corner, II-I2-I3-I4, set by Harvey Mellen, D.S. 1850.
Bearings were:
Spr. Pine 5", N56E, 12 Lks. and Spr. Pine 14", S62W, 38 Lks.
- M-6; East Quarter Corner, Sec. I3, set by Wm. A. Burt, D.S, July 13, 1840.
Bearings were:
Spruce 4", S15W, 30 Lks. and Pine 14", N17W, 8 Lks.
- K-4; Quarter Corner bet. Sec's. II-I2, set by H. Mellen, D.S. 1850.
Bearings were: Spr. Pine 5", N56E, 12 Lks. and Spr. Pine 14", S62W, 38 Lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- K-5; Found Corner as placed by D. C. De La Mater, RLS 10/29/52. Monument in place. Bearing Tree (R.Pine 20", N19W, 30.0') has been cut about 1958.
- M-6; Found two inch Iron Pipe set in concrete, in East edge of Road, set by Marcus Schaaf, RLS.
- K-4; Found Original Bearing Tree, S62W, 38 Lks. and a 2" Pipe, buried in Firelane. New Bearings, marked in 5/22/59. have been removed by a Logging Operation.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-5; Re-Witnessed Corner.
New Bearing; 9" R.Pine, N43E, 37.7"
- M-6; Witnessed Corner as I found it.
New Bearings: 16" R.Pine, N86E, 21.0' and 15" R.Pine, N60W, 50.4' and 15" R.Pine, S47W, 79.5'.
- K-4; Re- Witnessed Corner.
New Bearings:
5" J.Pine, S37E, 13.18 and 7" J.Pine, N67E, 18.4"

SIGNED BY Billy D. Buckler DATE 5/4/76.

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887.



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____