

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49. NR. 9. W. . .

----- Luce ----- COUNTY

DESCRIPTION OF CORNER 1/4 Section Corner between Sections 13 and 24 . . .

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap . . .

WITNESSES TO CORNER 15" Hemlock . . . N 39° W . . . 83 1/2 links . . .

15" Hemlock . . . S 86° W . . . 38 1/2 links . . .

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 Corner from remains of 50" W. Pine stump (possible B.T.)

Traces of axe marks on stump; possible scribe mark. Old W. Birch has been squared up at corner years ago. Several cruisers blazes on road 9 chs. East of here. Line blazed E. and W. Old squared stake on ground.

Bernard McTiver, District Forester, says this stump was in good condition about 25 years ago.

Corner placed and witnessed August 15, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckler . . . DATE 8/17/56 . . .
REGISTERED LAND SURVEYOR