

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
 Luce Co. Three Corners.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 49 N. R. 9 E. W.	C-2 3-Sec. 5 10-Sec. 5
2. PROPERTY CONTROLLING IN SECTION	5 T. 49 N. R. 9 E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 8/17 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- C-2 quarter corner bet. Secs: 5-6, set by Harvey Wellen, D.S. 1850.
 Bearings were:
 Sp. Pine 9" $N22^{\circ} E$ 21 lks. and Sp. Pine 12" $S54^{\circ} W$ 19 lks.
 - 3-Sec. 5 north 1/16 Corner, on west side of Section 5.
 - 10-Sec. 5 South 1/16 Corner, on West side of Section 5.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- C-2 Corner re-established on line and by single proportionate measure, bet. the Sec. Cors. Corner lies on East side of N-S firelane.
 - 3-Sec. 5 1/16 Corner established by single proportionate measure, bet. Sec. Cor. to North and 1/4 Cor. to South. Corner lies on top of river bank and in line with firelane to north.
 - 10-Sec. 5 1/16 corner established midway and on line bet. Sec. Cor. to South and 1/4 Cor. to North. Cor. lies in N-S firelane.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
 Placed 1" pipe with 4" aluminum cap at all three corners.
- C-2 New Bearings: 10" Jack Pine $S81^{\circ} W$ 24.8' and 8" Jack Pine $N46^{\circ} W$ 41.0'
 - 3-Sec. 5 Bearings: 10" Red Pine $N77^{\circ} W$ 43.5' and 10" Jack Pine $S15^{\circ} W$ 29.0'
 - 10-Sec. 5 Bearings: 9" Jack Pine $N78^{\circ} W$ 22.6' and 8" Jack Pine $N73^{\circ} E$ 22.7'

SIGNED BY Billy D. Buckler DATE 1/4/73

SURVEYOR'S MICHIGAN REGISTRATION NO. 5337 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____