

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
 Luce Co. Three Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>49</u> N. <u>3</u> , R. <u>9</u> E. <u>W.</u>	I-2 3-Sec.2 10-Sec.2
2. PROPERTY CONTROLLING IN SECTION <u>2</u>	T. <u>49</u> N. <u>3</u> , R. <u>9</u> E. <u>W.</u>	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. <u>W.</u>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 8/11 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:**
- I-2 1/4 Cor. bet. Secs: 2-3, set by Harvey Mellen, D.S. 1850.
 Bearings here:
 Sp. Pine 12" N17°W 46 lks. and Sp. Pine 10" S63°E 7.24 cr.
 - 3-Sec.2 North 1/16 Corner, on West side, Sec.2.
 - 10-Sec.2 South 1/16 Corner, on West side, Sec.2.
- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**
- I-2 Corner re-established midway and on line bet. two Sec. Cors.
 Corner lies on West side of N-S firelane.
 - 3-Sec.2 Corner established midway and on line bet. Sec. Cor. to North and 1/4 Cor. to South. Corner lies on West side of N-S firelane.
 - 10-Sec.2 Corner established midway and on line bet. Sec. Cor. to South and 1/4 Cor. to North. Corner lies on West side of N-S firelane.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- Placed 1" pipe with 4" aluminium cap at all three corners.
- I-2 New Bearings: 9" Jack Pine N89°E 32.2' and 9" Jack Pine N44°E 35.1'
 - 3-Sec.2 Bearings: 6" Jack Pine N68°E 36.6' and 6" Jack Pine S44°E 5.8'
 - 10-Sec.2 Bearings: 8" Jack Pine S77°W 34.2' and 9" Jack Pine S67°E 35.2'

SIGNED BY Billy D. Buckler DATE 1/4/73

SURVEYOR'S MICHIGAN REGISTRATION NO. 8807 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____