

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>49</u> <sup>N.</sup> <del>S.</del> , R. <u>9</u> <sup>E.</sup> <del>W.</del>	A-8
2. PROPERTY CONTROLLING IN SECTION _____	T. _____, <sup>N.</sup> <del>S.</del> , R. _____ <sup>E.</sup> <del>W.</del>	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____, <sup>N.</sup> <del>S.</del> , R. _____ <sup>E.</sup> <del>W.</del>	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 4/27 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

Original  $\frac{1}{4}$  Cor. on west side Sec. 19, set by John Burt D.S. for Wm A. Burt, D.S. in 1841.

**Bearings were:**

Cedar 4" S32°E 19Links  
Spruce 6" N29°W 20Links

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

Corner re-established by proportionate measurement and on a straight line bet. two Sec. Cors.

Found no evidence of original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Placed a 1" pipe with 4" aluminium cap at corner.

**New Bearings:**

10" Cedar N42°W 15.4'  
8" Cedar S28°E 22.6'

SIGNED BY *Billy D. Buckler* Billy D. Buckler DATE 6/29/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887 (SEAL)

**FOR STATE AND UNITED STATES AGENCIES:**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_