

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 49 N.R. 9 W


Luce COUNTY

DESCRIPTION OF CORNER M. C. North side Little Pike Lake between Secs. 16-15

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 9/1/65 with L. Rubick

WITNESSES TO CORNER..... 6" Tamarack (M.C. NBT), S 71° E, 08½ Lts.



4" Tamarack (M.C. NBT), N 32° W, 32½ Lts.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced from 2 Original BT's (6" Tamarack S 57½° W, 51 Lts.) and 5" Tamarack, N 28½° E, 121 Lts.) Both stumps in poor condition, scribe marks and overgrowth of scribe marks visible.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 11/16/1965  
REGISTERED LAND SURVEYOR