

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49 N.R. 9 W


Irce COUNTY

DESCRIPTION OF CORNER Section Corner for Secs. 14-15-22-23

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 9/1/65 with L. Hubick

WITNESSES TO CORNER..... 7" Cedar (S 22 NRT), S 41° W, 49 lks.



18" W. Pine (Original BT), S 81° E, 42 lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was placed at Scribed Wood Post. (W. Pine 6, N 81° E, 62 lks.) is growing but bearing is S 81° E instead of N 81° E. (W. Pine 12" S 47° E 27 lks) is a 3 ft stub in poor condition, has notch and overgrowth and is in proper position.

SURVEYOR'S SEAL

Frank J. Bray
SIGNED Frank J. Bray DATE 11/16/1965
REGISTERED LAND SURVEYOR