

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 49. NR. 9. W. . .

Luce

COUNTY

DESCRIPTION OF CORNER Section Corner Common to Sections 2-3-10-11

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 12" Jackpine (S10 NBT) S 69° W. 75 Links

13" Jackpine (S11 NBT) S 70° E. 45 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Corner as set by Marcus Schaaf, Reg. Surveyor. Found 2" Iron Pipe in place with remains of Jackpine B.T. N 33° E 155 Links. Found wood slabs set at B.T. sites.

Corner lies in Intersection of N-S-E-W Firelanes.

Shown to us by B. McTiver, District Forester.

Corner placed and witnessed May 29, 1958.

SURVEYORS SEAL

SIGNED *Billy D. Buckler*  
Billy D. Buckler  
REGISTERED LAND SURVEYOR

DATE 12/3/58