

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49. NR. 9. W. . .

----- Iuce ----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 22, 23, 26, 27.

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER 6" White Pine -- N 60° E -- 115 links -----

5" White Pine -- N 68° W -- 58 links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Section Corner from one White Pine B.T. rotted; notch remaining on stump.

Squared post in place.

Corner lies in marsh and SE of small pond.

Corner shown to us by Gerald Kutchera, Assistant District Forester.

Corner placed and witnessed August 15, 1956.

SURVEYORS SEAL

SIGNED Billy D. Buckler -- DATE 8/17/56 --
REGISTERED LAND SURVEYOR