

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 49N N.R. 9W


Luce COUNTY

DESCRIPTION OF CORNER 1/4 Cor. bet. Secs. 22-27

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 9-14-70

WITNESSES TO CORNER..... 14" Red Pine (1/4 S NBT) N15°W 12.3'



CIRCLE CORNER REGISTERED

12" White Pine (1/4 S NBT) N15°W 70.9'

AND

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner re-established midway and on line bet. two Sec. Cors.  
Found a wood post on ground but no evidence of two small jack pine witnesses.  
Corner lies 15.0' east of top of ridge as indicated in the record notes.

**SURVEYOR'S SEAL**

*Billy D. Buckler*  
SIGNED Billy D. Buckler DATE 9-23-70  
REGISTERED LAND SURVEYOR