

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 49N N.R. 9W


Luce COUNTY

DESCRIPTION OF CORNER ¼ Cor. bet. Secs. 21-22

CORNER MONUMENT 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 9-4-70

WITNESSES TO CORNER..... 8" Red Pine (¼S NBT) N45°E 11.7'



8" Red Pine (¼S NBT) S42°E 7.3'

9" Red Pine (¼S NBT) N64°W 7.1'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner replaced from remains of two original Y. Pine witnesses; both are stumps with lower face and notch in evidence, bearing 10°E, 31 lks and N76°W, 20 lks. Cor. found by L. Rubick, Forestry Aide.

Cor. lies on top of pine ridge, running east and west, between two swamps.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler* DATE 9-21-70
REGISTERED LAND SURVEYOR